BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Improvements to Toilet works in Ward No.07

Work Order No: EE (Project)/Ynk Zone/WO/ 16/2020-21 Dt:- 13/05/2020

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. U RAMESH	
				In figures	In words
1	6.30	SOLID PVC DOOR FRAME Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size	Cum	530.51	Rupees Five Hundred Thirty And Paise Fifty One Only
2	6.30	SOLID PANEL PVC DOOR SHUTTER Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19x19mm fro styles and 15x15mm for top & bottom rails, covered with heat moulded PVC channel of 5mm thick sheet & 30 x 50mm wide to form styles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the styles & rails with 5x30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 m.m Aluminium hinges.	Cum	3147.92	Rupees Three Thousand One Hundred Forty Seven And Paise Ninety Two Only
3	6.00	Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580 x 440mm with integral type footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Cum	4788.19	Rupees Four Thousand Seven Hundred Eighty Eight And Paise Nineteen Only
4	18.90	Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 30x30cms 6mm thick.	Cum	1371.62	Rupees One Thousand Three Hundred Seventy One And Paise Sixty Two Only
5	25.20	Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 - Colour glazed tiles 15x15 cms 6mm thick	Cum	1440.76	Rupees One Thousand Four Hundred Forty And Paise Seventy Six Only
6	25.20	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Cum	100.89	Rupees One Hundred And Paise Eighty Nine Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

	Quantity	Item Name	Unit	Approved Rates of Sri. U RAMESH	
				In figures	In words
7	32.40	Providing & applying aluminium paint one coat (excluding primer coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt & other foreign matter, including cost of materials, labour, complete as per specifications.	Cum	54.41	Rupees Fifty Four And Paise Forty One Only
8	1.00	Atalanta,Suguna,CRI KIRLOSKER AND other equipment pumps 1.00 HP (10 Stage	Nos	14991.44	Rupees Fourteen Thousand Nine Hundred Ninety One And Paise Forty Four Only
9	30.00	Providing and fixing chorinated poly vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) 50mm nominal OD pipes	Mtr	527.11	Rupees Five Hundred Twenty Seven And Paise Eleven Only
10	50.00	Providing and fixing chorinated poly vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) 32mm nominal OD pipes	Mtr	287.93	Rupees Two Hundred Eighty Seven And Paise Ninety Three Only
11	6.24	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications.	Sqm	810.50	Rupees Eight Hundred Ten And Paise Fifty Only
12	20.00	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 6mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) including cost of materials, labour, HOM complete as per specifications.	Mtr	973.73	Rupees Nine Hundred Seventy Three And Paise Seventy Three Only
13	18.00	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Mtr	2452.92	Rupees Two Thousand Four Hundred Fifty Two And Paise Ninety Two Only
14		GST @ 12%			

13/

Contractor

Executive Engineer
Project Division
Yelahanka Zone